

Portata max raccomandata in dm^3/sec di aria libera attraverso tubazioni in acciaio serie media dimensionate a norme ISO 65

Max suggested flow rate in dm^3/sec of free air through steel tubes medium series according normative ISO 65

Pressione di prova* (bar) Testing pressure* (bar)	Passaggio nominale (in pollici e mm) / Nominal passage (inch and mm)										
	1/8 6 mm	1/4 8 mm	3/8 10 mm	1/2 15 mm	3/4 20 mm	1 25 mm	1 1/4 32 mm	1 1/2 40 mm	2 50 mm	2 1/2 65 mm	3 80 mm
0.4	0.3	0.6	1.4	2.6	4	7	15	25	45	69	120
0.63	0.4	0.9	1.9	3.5	5	10	20	30	60	90	160
1	0.5	1.2	2.8	4.9	7	14	28	45	80	130	230
1.6	0.8	1.7	3.8	7.1	11	20	40	60	120	185	330
2.5	1.1	2.5	5.5	10.2	15	28	57	85	170	265	470
4	1.7	3.7	8.3	15.4	23	44	89	135	260	410	725
6.3	2.5	5.7	12.6	23.4	35	65	133	200	390	620	1085
8	3.1	7.1	15.8	29.3	44	83	168	255	490	780	1375
10	3.9	8.8	19.5	36.2	54	102	208	315	605	965	1695
12.5	4.8	10.9	24.1	44.8	67	127	258	390	755	1195	2110
16	6.1	13.8	30.6	56.8	85	160	327	495	955	1515	2665
20	7.6	17.1	38	70.6	105	199	406	615	1185	1880	3315

*I valori di pressione di prova sono quelli indicati dalle norme ISO 2944

The values of testing pressure are indicated on normative ISO 2944